GREENROUTE

SCREENING REPORT

Request evidence before credit review

Preliminary screening for the bank's reviewer, not a credit decision

DEMO UNIVERSITY (SYNTHETIC) / AMMAN

Campus energy upgrade

1 Summary

REQUESTED **JOD 553,000** 4 upgrades	**CANDIDATE SCOPE** **JOD 430,000** Solar + LED / proof required	**RETURN OR COMPLETE** **JOD 123,000** Library + water
ANNUAL SAVINGS **JOD 373,632** Illustrative screening result	**COVERAGE** **4.3x** 3.0x at 70% savings	**IMPACT** **1459.5 MWh** 649 tCO2e / year

NEXT ACTION Request the missing evidence, then specialist review. The bank retains eligibility and credit decisions.

Scope by upgrade

Each status is a screening judgment, not an approval. Amounts and rules are unchanged.

SOLAR PV

JOD 250,000

CONDITIONAL / PROOF MISSING

SCREENING REASON

Eligible activity is plausible, but supplier forecast is not verified and end-of-life proof is missing.

EVIDENCE NEEDED

Forecast method or measured site output; panel recycling plan.

LED LIGHTING

JOD 180,000

CONDITIONAL / PROOF MISSING

SCREENING REASON

50% benchmark is used instead of the 70% supplier claim. Line B listing is absent.

EVIDENCE NEEDED

LED line B efficiency class or ENERGY STAR listing.

LIBRARY RETROFIT

JOD 85,000

NOT MET

SCREENING REASON

Claimed 14% reduction is below the 20% whole-building rule; baseline is also absent.

EVIDENCE NEEDED

EPC or RSS BEP assessment and 12+ months adjusted bills.

WATER FIXTURES

JOD 38,000

UNKNOWN / CANNOT SCREEN

SCREENING REASON

The 30% brochure claim has no measured baseline or qualifying product labels.

EVIDENCE NEEDED

12 months water bills, tariff, and JS 1945:2011 or WaterSense-type labels.

Evidence inventory

Supplier claims are not verified evidence. Credit-only files are not green proof.

DOCUMENT	QUALITY	WHAT IT SUPPORTS / WHY UNUSABLE
Solar_Quote_FINAL_v3.pdf	**Supplier claim**	Supplier claim is not verified. 20 Aug 2026 supplier quote. 500 kWp on roofs and car-park shades. Price JOD 250,000. Projected yield 1,800 kWh/kWp/year. Valid 60 days. This is a supplier claim, not measured generation.
Solar_Quote_FINAL_v3 (1).pdf	**Exact duplicate**	Set aside: 20 Aug 2026 supplier quote. 500 kWp on roofs and car-park shades. Price JOD 250,000. Projected yield 1,800 kWh/kWp/year. Valid 60 days. This is a supplier claim, not measured generation.
Fwd_ Solar quote.pdf	**Duplicate text**	Set aside: 20 Aug 2026 supplier quote. 500 kWp on roofs and car-park shades. Price JOD 250,000. Projected yield 1,800 kWh/kWp/year. Valid 60 days. This is a supplier claim, not measured generation.
PV_modules_and_inverters_datasheets.pdf	**Certificates missing**	Monocrystalline panels and three-phase string inverter. Manufacturer certificates are mentioned, but copies have not been submitted.
LED_offer_2026.pdf	**Supplier claim**	Supplier claim is not verified. 25 Aug 2026 supplier offer. Classroom and office panel line A; high-bay and outdoor line B. Price JOD 180,000. Supplier claims up to 70% lighting saving. This claim is not measured.
LED_panel_lineA_ENERGY_STAR.pdf	**Line A only**	Product sheet shows ENERGY STAR listing for LED panel line A only. It does not establish certification for high-bay/outdoor line B.

Evidence inventory / continued

Remaining screening, set-aside and credit-only records.

DOCUMENT	QUALITY	WHAT IT SUPPORTS / WHY UNUSABLE
Library_upgrade_proposal.pdf	**Baseline missing**	30 Jul 2026 contractor proposal. Main library 6,000 m2, window film and HVAC controls. Cost JOD 85,000. Claims 14% whole-building reduction. Measured baseline and performance proof are absent.
Water_saving_fixtures_brochure.pdf	**Baseline missing**	1 Jun 2026 brochure. Taps and dual-flush toilets, JOD 38,000. Claims up to 30% water saving. Baseline and product labels are absent.
Electricity_bill_March_2019.pdf	**Stale / replace**	March 2019 electricity bill. Historical bill only; cannot establish the current electricity baseline.
scan_0012.pdf	**Unreadable / replace**	[Image-only scan. No readable text could be extracted. Request a legible copy.]
Grid_connection_application_receipt.pdf	**Study pending**	1 Sep 2026 receipt of grid-impact study application. The study is pending. This receipt is not grid approval.

Evidence inventory / continued

Remaining screening, set-aside and credit-only records.

DOCUMENT	QUALITY	WHAT IT SUPPORTS / WHY UNUSABLE
Campus_newsletter_Spring_2026.pdf	**Irrelevant**	Set aside: Spring 2026 newsletter: graduation, football and cafeteria updates. No project screening evidence.
About_Demo_University_2026.pdf	**Context only**	Credit-only, not green proof. Institution background and admissions overview. This is context for credit staff, not evidence of repayment capacity.
Solar_generation_forecast_2026.pdf	**Method missing**	22 Aug 2026 supplier projection: 500 kWp at 1,800 kWh/kWp/year. No forecast method or measured site output is provided.
Campus_energy_feasibility_study.pdf	**Unconfirmed total**	26 Aug 2026 feasibility study. Solar JOD 250,000, LED JOD 180,000, library JOD 85,000, water JOD 38,000. Total JOD 553,000. Savings are estimated from supplier claims. No verified operating baseline, university cash flow or debt schedule.
Institution_financial_summary_2026.pdf	**Unaudited**	Credit-only, not green proof. 27 Aug 2026 management revenue and cash forecast only. Audited financial statements, existing debt schedule and debt-service history have not been submitted. No repayment conclusion can be drawn.

Data checks

Findings distinguish published benchmarks, arithmetic corrections, stand-ins and evidence gaps.

Solar yield forecast

CORRECTED

SUBMITTED	REFERENCE OR SCREENING INPUT	FINDING / MEANING
1,800 kWh/kWp/year	1,639 kWh/kWp/year / Published benchmark / S10 p.1	Supplier forecast corrected for screening; site output remains unverified.

Solar price

MATCHES

SUBMITTED	REFERENCE OR SCREENING INPUT	FINDING / MEANING
JOD 500 / kW	JOD 500 / kW / Brief-supplied scenario / S13 citation missing	The numbers match, but this is not a verified published benchmark.

LED saving

CORRECTED

SUBMITTED	REFERENCE OR SCREENING INPUT	FINDING / MEANING
70%	50% / Published benchmark / S12 p.91	Use 50% for screening, not the supplier's unmeasured 70% claim.

Data checks / continued

Findings distinguish published benchmarks, arithmetic corrections, stand-ins and evidence gaps.

Lighting share

CONFLICT

SUBMITTED	REFERENCE OR SCREENING INPUT	FINDING / MEANING
3.2%	32% / Arithmetic from 32 / 100	Printed 3.2% conflicts with the underlying arithmetic; 32% is used.

Campus electricity

STAND-IN

SUBMITTED	REFERENCE OR SCREENING INPUT	FINDING / MEANING
No bills	4,000,000 kWh/year / 4 GWh stand-in / S10 p.1; permitted as intermediate by S17 p.5	Not campus evidence. Replace with 12 months of current bills.

Library and water baselines

CANNOT CHECK

SUBMITTED	REFERENCE OR SCREENING INPUT	FINDING / MEANING
Library 14%; water 30%	Cannot verify either claim / No benchmark can replace project baselines	Library and water claims cannot be checked.

Compliance matrix

Statuses reproduce the demo compliance mapping. They are screening outcomes, not an eligibility or credit approval.

NATIONAL GREEN TAXONOMY / S09

		BLOCKER / BASIS	NEXT ACTION
Solar PV activity	MET	Solar PV is an eligible activity.	Continue evidence review
Do no significant harm	PROOF MISSING	The recycling plan for end-of-life panels is missing.	Request recycling plan
LED lighting replacement	PROOF MISSING	Line B has no listing.	Request line B listing
Building renovation	NOT MET	The design saves 14%; the whole building must cut energy use by at least 20%. EPC or RSS BEP baseline proof is also absent.	Return or redesign; provide EPC / RSS BEP proof
Water fixtures	PROOF MISSING	Fixture standards and labels have not been provided.	Request product labels

Compliance matrix / continued

These are separate rule layers. A green-screening status does not determine credit approval.

BANK GREEN FRAMEWORK / S03

		BLOCKER / BASIS	NEXT ACTION
Renewable energy	MET	Aligned with eligible green categories.	Specialist eligibility review
Library energy efficiency	NOT MET	The library design saves 14%; the bank framework requires at least 20%.	Return or redesign; provide performance evidence

PERMITS + ENERGY RULES / S18

		BLOCKER / BASIS	NEXT ACTION
Grid connection approval	PROOF MISSING	Formal study and approval pending.	Obtain formal approval

BANK-RUN CHECKS / S17

		BLOCKER / BASIS	NEXT ACTION
Climate risk assessment	BANK REVIEW	Required for institutional lending.	Bank completes review

Project analysis

Screening arithmetic only. Savings, assumptions and loan illustration are not bank terms.

ANNUAL SAVINGS FORMULA

1459.5 MWh x 1,000 kWh/MWh x 0.256 JOD/kWh

= JOD 373,632 per year

STRESS COVERAGE

ASSUMPTIONS / NOT BANK TERMS

CANDIDATE PRINCIPAL

JOD 344,000 / 80% of candidate scope

ILLUSTRATIVE FINANCING

8% assumed / 5 years / JOD 86,157 annual payment

SYNTHETIC DERIVATIONS

500 kWp from cost / price; 1280 MWh lighting baseline from stand-in campus use

IMPACT FACTOR

0.4447 tCO2e/MWh / S12 p.29 / 649 tCO2e per year

Evidence requests

Request now: 8 items. Received items awaiting confirmation are not requested again.

UNIVERSITY FINANCE OFFICE

01 Electricity bills, last 12 months

WHY NEEDED
Replace the campus electricity stand-in with a current operating baseline.

STAGE
Request now / preliminary screening

02 12 months of water bills

WHY NEEDED
Establish current water consumption before testing the savings claim.

STAGE
Request now / preliminary screening

03 The water tariff the campus pays

WHY NEEDED
Convert measured water savings into a supported financial estimate.

STAGE
Request now / preliminary screening

RECEIVED / AWAITING CONFIRMATION / DO NOT REQUEST AGAIN

Solar forecast / LED line A listing / Library proposal / Water fixtures brochure / Grid study receipt / Feasibility study

LATER STAGES

Before payout: grid-connection approval; municipality permit plus electrical-safety sign-off. Credit team: legal identity; 3 years audited statements; debt schedule; governance.

Evidence requests / Facilities and engineering

FACILITIES AND ENGINEERING

01 EPC or RSS BEP assessment for the library

WHY NEEDED

Test the whole-building reduction against the 20% rule.

STAGE

Request now / preliminary screening

02 12+ months of the library's bills, adjusted for weather and occupancy

WHY NEEDED

Create a weather- and occupancy-adjusted library baseline.

STAGE

Request now / preliminary screening

Evidence requests / Suppliers and contractors

SUPPLIERS AND CONTRACTORS

01 End-of-life and recycling plan for the panels

WHY NEEDED
Address the taxonomy recycling requirement for PV panels.

STAGE
Request now / preliminary screening

02 LED line B efficiency class or ENERGY STAR listing

WHY NEEDED
Line A evidence does not establish line B eligibility.

STAGE
Request now / preliminary screening

03 Fixture specs showing JS 1945:2011 or a WaterSense-type label

WHY NEEDED
Show that fixtures meet JS 1945:2011 or a WaterSense-type label.

STAGE
Request now / preliminary screening

Limits + source register

Bills, baselines, labels, permits and audited financials are incomplete. Assumptions are intermediate screening inputs, not proof.

S03 SOURCE LOCATED

Jordan Ahli Bank Sustainable Finance Framework

Jordan Ahli Bank / June 2024

PASSAGES: p.22, p.14, p.19, p.16

S09 SOURCE LOCATED

Jordan National Green Taxonomy

Central Bank of Jordan and Ministry of Environment / January 2026

PASSAGES: p.3, p.86, p.86, p.132, p.136, p.138

S10 SOURCE LOCATED

First Year Performance of a PV Plant in Jordan Compared to PV Plants in the Region

Hamzeh et al. / 2015

PASSAGES: p.1, p.1

S11 SOURCE LOCATED

Jordan electricity tariff guide effective 1 January 2025

Energy and Minerals Regulatory Commission / 1 January 2025

PASSAGES: p.7

S12 SOURCE LOCATED

Third National Energy Efficiency Action Plan 2024-2026

Ministry of Energy and Mineral Resources / 2024-2026

PASSAGES: p.91, p.29, p.3

S13 CITATION MISSING

Published home-solar price (citation needed)

Publication not provided / Date not provided

PASSAGES: no page

S17 SOURCE LOCATED

CBJ Climate Risk Management Regulations No. 2 of 2025

Central Bank of Jordan / 2025

PASSAGES: p.4, p.5

S18 SOURCE LOCATED

Jordan PV installation process guide

EBRD GEFF Jordan / 2024

PASSAGES: p.5, p.8

Appendix / source passages

Quoted text is separated from analyst summaries. Badges identify source and page.

S03 / P.22 — EXACT QUOTE

In general, an EE project must reduce absolute energy consumption by at least 20%.

S03 / P.14 — EXACT QUOTE

Eligible Loans will need to satisfy the standard due diligence process as part of Jordan ahli bank's lending assessment.

S03 / P.19 — EXACT QUOTE

Annual energy savings (MWh); or Estimated annual GHG emission avoided (tCO2e)

S03 / P.16 — SUMMARY

final eligibility check by the E&S officer.

S09 / P.3 — EXACT QUOTE

It does not prescribe or restrict lending, investment, or financing decisions

S09 / P.86 — EXACT QUOTE

The activity generates electricity, heating or cooling using solar PV or other solar energy-based technologies.

S09 / P.86 — EXACT QUOTE

End-of-life management for PV panels are implemented in accordance with recycling standards and best practices.

Appendix / source passages continued

Quoted text is separated from analyst summaries. Badges identify source and page.

S09 / P.132 — SUMMARY

taps, showers and WCs must meet JS 1945:2011 or carry a WaterSense-type label.

S09 / P.136 — SUMMARY

The whole building must cut energy use by at least 20%. Buildings over 1,000 m2 prove it with the Jordanian EPC or the RSS BEP tool from adjusted bills.

S09 / P.138 — EXACT QUOTE

comply with the two highest populated efficiency classes of relevant Jordanian energy-efficiency labels (JSMO), where such labels exist, or carry an ENERGY STAR listing.

S10 / P.1 — EXACT QUOTE

the actual and estimated specific energy productions are 1639kWh/kWp-year, and 1726 kWh/kWp-year

S10 / P.1 — EXACT QUOTE

The annual electricity consumption is about 4 GWh [1].

S11 / P.7 — SUMMARY

educational tariff of 256 fils per kWh

S12 / P.91 — EXACT QUOTE

can reach up to 70%, with an average of around 50%

Appendix / source passages continued

Quoted text is separated from analyst summaries. Badges identify source and page.

S12 / P.29 — SUMMARY

0.4447 tCO2e per MWh

S12 / P.3 — SUMMARY

earlier national plans delivered 40.2% and 46.3% of their targets.

S13 / PAGE NOT PROVIDED — SUMMARY

About JOD 500 per kW - benchmark supplied in the project brief; publication link and exact passage pending.

S17 / P.4 — SUMMARY

climate checks during credit processing, including environmental approvals

S17 / P.5 — SUMMARY

where reliable data is missing, banks may use reasonable assumptions as an intermediate step.

S18 / P.5 — SUMMARY

the distribution company runs a grid-impact study, then gives approval

S18 / P.8 — SUMMARY

municipality approval to operate.

APPENDIX B / RECORD OF CHANGES

Inputs and source register loaded from @workspace/greenroute-research; supplier claims corrected or labelled as stand-ins; local request history retained.